

Snively Avenue Road and Utility Improvement Project - Addendum No. 1

NOTICE TO BIDDERS

The following changes in the Bidding and Contract Documents, including the Drawings and Specifications for **Snively Avenue Road and Utility Improvement**, constitute this **Addendum No. 1, dated March 22, 2021**. All changes included in addenda issued prior to bid date shall become a part of the Contract Documents for this Project. Any changes herein offset only the Specific Drawings, notes on Drawings or words or paragraphs in Specifications referenced. The balance of the Drawings shall remain in full force. Acknowledge receipt of this Addendum by inserting its number and date in space provided in Bid Proposal Form. Failure to do so may subject Bidder to disqualification.

GENERAL

<u>ITEM NO.</u>	<u>ITEM</u>	<u>DESCRIPTION</u>
G1.01	Bid Date	Bid Date shall be revised to March 31, 2021.
G1.02	Article 23 of the Bidder's Instructions	Delete the section. The portion of water main work within the BNSF right-of-way has been deleted from project.
G1.03	Permits	A no fee Right-of-Way permit with traffic plan will be required to be submitted by contractor prior to start of construction.

SPECIFICATIONS

<u>ITEM NO.</u>	<u>SECTION</u>	<u>DESCRIPTION</u>
S1.01	333111-2 – 2.3A	Cleanouts shall be standard typical install per City of Chehalis Detail 5-10 on sheet C1.2. Delete section 333111 2.3 from the specifications.

Snively Avenue Road and Utility Improvement Project - Addendum No. 1

PLANS

<u>ITEM NO.</u>	<u>SHEET NO.</u>	<u>DESCRIPTION</u>
P1.01	C1.0	<p>Delete all water main improvements within the BNSF right-of-way. Connect to existing watermain at BNSF right of way.</p> <p>Add two fittings</p> <p> STA 0+55, 14 'RT</p> <p> 1 – 4" 45 deg Bend</p> <p> Blocking</p> <p> STA 0+67, 5' right</p> <p> 1 – 8 x 4 Tee Fitting</p> <p> 1 – 8" Valve</p> <p> 1 – 4" 45 deg Bend</p> <p> Blocking</p> <p>Provide 12 LF 8" DI W.M. between fittings</p> <p>Revise 418 LF 8" DI WM to 393 LF</p>
P1.02	C1.0 and C1.2	<p>Please note Sewer construction notes 4 and 5. Contractor will be required to connect new sewer laterals to each lots existing side sewer.</p> <p>④ PROVIDE AND INSTALL NEW SANITARY SEWER BUILDING LATERALS TO EACH LOT. CONTRACTOR TO VIDEO EXISTING SEWER MAIN TO FIELD LOCATE INDIVIDUAL LATERAL LOCATIONS PRIOR TO CONSTRUCTION START.</p> <p>⑤ CONTRACTOR SHALL CONNECT THE NEW SEWER LATERALS TO CUSTOMER LATERAL AT THE PROPERTY LINE. PROVIDE CLEANOUT BETWEEN BACK OF NEW CURB AND RIGHT OF WAY LINE. SEE CITY STANDARD DETAIL ON SHEET C1.2.</p>
P1.03	C2.0 and C2.1	Delete plan sheets from bid and all water main work within the BNSF Right-of-Way.
P1.04	C3.3	Delete 4" New CSTC surfacing within the BNSF Right-of-Way.
P1.05	C4.1	Delete Clearing limits within the BNSF Right-of-Way

Attachments:

End of Addendum